



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY

# PLACER COUNTY OFFICES OF EDUCATION NEW MAIN OFFICE HVAC PACKAGE UNIT REPLACEMENT

1400 STANFORD RANCH, ROCKLIN CA 95765



Delta	Date	Revisions	By

**GENERAL NOTES**

- ALL WORK SHALL BE IN ACCORDANCE WITH REQUIREMENTS OF GOVERNING CODES LISTED IN "APPLICABLE CODES" AND ALL GOVERNING LOCAL CODES AND REGULATIONS.
- THE OWNER / ARCHITECT HAVE OBTAINED APPROVAL OF THE PRIMARY AUTHORITY HAVING JURISDICTION (DSA, HCAI, CITY BUILDING PERMIT). CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL OTHER REQUIRED PERMITS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- UNLESS STATED OTHERWISE IN THE SPECIFICATIONS, SPECIAL INSPECTION IS REQUIRED FOR SHOP AND FIELD STRUCTURAL WELDING.
- WHERE INCORPORATED IN THE CONSTRUCTION, IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN COPIES OF HCAI OR DSA PRE-APPROVALS FOR PRE-APPROVED ITEMS OR SYSTEMS INCORPORATED INTO THE CONSTRUCTION AND DISTRIBUTE TO OWNER'S REPRESENTATIVE, ARCHITECT AND INSPECTOR.
- IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO FURNISH AND INSTALL ALL MATERIALS AND WORK DESCRIBED, DEPICTED OR DETAILED WITHIN THESE DOCUMENTS REGARDLESS OF THE LOCATION OF THAT MATERIAL OR WORK WITHIN THE DOCUMENTS OR OMISSION (WHETHER DELIBERATE OR ACCIDENTAL) OF THAT MATERIAL OR WORK BY A SUBCONTRACTOR ON HIS/HER BID.
- THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL CONSIDER THESE DOCUMENTS IN THEIR ENTIRETY. DISCREPANCIES OR CONTRADICTIONS BETWEEN PORTIONS OF THESE DOCUMENTS MUST BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AT LEAST 72 HOURS PRIOR TO BID OPENINGS FOR CLARIFICATION. OTHERWISE, THE MOST RESTRICTIVE REQUIREMENT SHALL BE IN FORCE AT NO ADDITIONAL COST TO THE OWNER.
- THE CONTRACTOR SHALL ASSUME SOLE RESPONSIBILITY FOR THE SAFETY OF ALL PERSONS ON OR ABOUT THE CONSTRUCTION SITE, IN ACCORDANCE WITH APPLICABLE LAWS AND CODES. CONTRACTOR ESTABLISH PROCEDURES TO ASSURE ALL PERSONS ENTERING A POSSIBLY HAZARDOUS AREA, INCLUDING WORKERS, SUBCONTRACTORS, OTHER CONTRACTORS, VISITORS, AND OTHERS ARE AWARE OF APPROPRIATE / REQUIRED SAFETY PROCEDURES. COMPLY WITH LOCAL, STATE, AND FEDERAL SAFETY STANDARDS, INCLUDING OSHA REQUIREMENTS AND WITH THE SAFETY PROVISIONS OF THE LATEST MANUAL OF ACCIDENT PREVENTION PUBLISHED BY THE ASSOCIATED GENERAL CONTRACTORS OF AMERICA.
- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND MAINTAINING TEMPORARY FENCING AND GATES, SIGNAGE, SECURITY LIGHTING OR OTHER SECURITY AND CONTROL MEASURES NECESSARY TO PROVIDE FOR THE SAFETY OF THE PUBLIC AND FACILITY USERS UNTIL THE COMPLETION OF THE WORK.
- THE CONTRACTOR IS RESPONSIBLE TO FOR PROTECTION OF ADJACENT PROPERTY AND SHALL REPAIR AND / OR REPLACE ALL PROPERTY DAMAGED DURING THE COURSE ON THE WORK.
- THE CONTRACTOR SHALL LIMIT HIS / HER ACTIVITY TO THE AREA DESCRIBED WITHIN THE DOCUMENTS UNLESS OTHERWISE PERMITTED BY THE OWNER'S REPRESENTATIVE.
- THE CONTRACTOR IS RESPONSIBLE FOR THE REPAIR OR REPLACEMENT OF ANY ITEMS DAMAGED OR DISTURBED DURING THE COURSE OF THE WORK. INSTALLATION SHALL MATCH EXISTING IN KIND, QUALITY, AND PERFORMANCE.
- WHERE EXISTING CONSTRUCTION AND FINISHES ARE CUT, DAMAGED, OR REMODELED, PATCH WITH MATERIALS TO MATCH IN KIND, QUALITY, PERFORMANCE CHARACTERISTICS, AND APPEARANCE.
- ALL DIMENSIONS ARE TO FACE OF STUD, UNLESS OTHERWISE NOTED. DIMENSIONS NOTED AS "CLR" MEAN CLEAR DIMENSION TO FACE OF FINISH. VERIFY ALL EXISTING DIMENSIONS AND CONDITIONS AND NOTIFY ARCHITECT OF ANY DISCREPANCIES FOUND.
- VERIFY ALL EXISTING DIMENSIONS AND CONDITIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES FOUND. VERIFY DIMENSIONS OF ALL OWNER-FURNISHED ITEMS, INCLUDING FURNITURE AND EQUIPMENT, TO ENSURE PROPER COORDINATION WITH CONSTRUCTION.
- ALL ITEMS IN THESE DRAWINGS ARE NEW UNLESS OTHERWISE NOTED.
- ALL UTILITIES REQUIRED FOR THE CONTINUOUS OPERATION OF ALL OCCUPIED EXISTING FACILITIES SHALL BE MAINTAINED IN SERVICE AT ALL TIMES. ANY SHUT DOWNS FOR NEW CONNECTIONS MUST BE COORDINATED WITH THE OWNER'S REPRESENTATIVE TWO WEEKS PRIOR TO THE REQUESTED SHUT DOWN.
- COORDINATION WITH OTHER CONTRACTS: IF ANY PART OF THIS CONTRACTOR'S WORK DEPENDS UPON THE WORK OF A SEPARATE CONTRACTOR, THIS CONTRACTOR SHALL INSPECT SUCH OTHER WORK AND PROMPTLY REPORT IN WRITING TO THE OWNER'S REPRESENTATIVE ANY DEFECTS IN SUCH OTHER WORK THAT RENDER IT UNSUITABLE TO RECEIVE THE WORK OF THIS CONTRACTOR. FAILURE OF THIS CONTRACTOR TO SO INSPECT AND REPORT SHALL CONSTITUTE AN ACCEPTANCE OF THE OTHER CONTRACTOR'S WORK, EXCEPT AS TO DEFECTS WHICH MAY DEVELOP IN OTHER CONTRACTOR'S WORK AFTER EXECUTION OF THIS CONTRACTOR'S WORK.
- COORDINATION OF SCHEDULE: PORTIONS OF THIS WORK MAY BE REQUIRED TO BE COMPLETED ON SCHEDULE IN ORDER TO AVOID DELAY TO OTHER CONTRACTORS OR OWNERS OPERATIONS. CONTRACTOR SHALL STRICTLY ADHERE TO ESTABLISHED COMPLETION DATES AS DESIGNATED IN THE SPECIFICATIONS AND COORDINATE WORK SCHEDULE WITH THE OWNER'S REPRESENTATIVE AND OTHER CONTRACTORS. SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS AND LIQUIDATED DAMAGES.
- SCHEDULE ALL WORK WITH THE OWNER'S REPRESENTATIVE, INCLUDING CONSTRUCTION ACCESS AND STORAGE, AND WORK OUTSIDE THE "EXTENT OF WORK" SET FORTH IN THESE DOCUMENTS. THE CONSTRUCTION SCHEDULE SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO THE START OF CONSTRUCTION.
- CONSTRUCTION PROCEDURES SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO THE START OF CONSTRUCTION.
- DEMOLITION IS NOT NECESSARILY LIMITED TO ONLY WHAT IS SHOWN ON THIS OR OTHER DRAWINGS OR AS OUTLINED IN THE SPECIFICATIONS. THE INTENT IS TO INDICATE GENERAL SCOPE OF DEMOLITION REQUIRED. CONTRACTOR SHALL INCLUDE ALL MISCELLANEOUS DEMOLITION, CUTTING AND PATCHING REQUIRED TO COMPLETE THE PROJECT IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS.
- ALL ITEMS IDENTIFIED TO BE SALVAGED SHALL BE DELIVERED IN GOOD CONDITION TO A PLACE OF STORAGE AS DIRECTED BY THE OWNER'S REPRESENTATIVE. ALL OTHER ITEMS MUST BE DISPOSED OF OFF-SITE IN A LEGAL MANNER.
- ARCHITECT IS NOT RESPONSIBLE FOR THE DISCOVERY, PRESENCE, HANDLING, REMOVAL OR DISPOSAL OF, OR EXPOSURE OF PERSONS TO, HAZARDOUS MATERIALS OR TOXIC SUBSTANCES IN ANY FORM AT THE PROJECT SITE. TO THE EXTENT THESE DOCUMENTS RELATE TO SUCH ISSUES, ARCHITECT'S PARTICIPATION IS SOLELY ADMINISTRATIVE WITHOUT ANY RESPONSIBILITY FOR THE CONTENT OR EXECUTION OF SUCH DOCUMENTS.
- DETAIL DRAWINGS WITH REFERENCES TO FIRE-RATED ASSEMBLIES OR CONSTRUCTION WHICH HAVE BEEN TESTED BY UNDERWRITERS LABORATORIES, THE CALIFORNIA BUILDING CODE OR ANY OTHER APPROVED TESTING AGENCY, SHALL BE CONSTRUED TO INCLUDE ALL WORK AND PROCEDURES CONTAINED IN THE REFERENCED ASSEMBLY DESCRIPTION.
- ALL PIPE AND DUCT PENETRATIONS THROUGH FIRE RATED CONSTRUCTION SHALL BE FIRE STOPPED AND SEALED TO MAINTAIN THE REQUIRED RATING.
- CONTRACTOR TO MAINTAIN CONTEMPORANEOUSLY RECORDED "AS-BUILT" INFORMATION OF ALL WORK WHICH SHALL BE MARKED IN COLOR ON THE DRAWINGS AND SPECIFICATIONS. A SCANNED PDF OF THE "AS-BUILT" DRAWINGS AND SPECIFICATIONS SHALL BE TURNED OVER TO THE OWNER'S REPRESENTATIVE PRIOR TO FINAL APPLICATION FOR PAYMENT. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
- CONTRACTOR SHALL PROVIDE TEMPORARY PROTECTION AND DUST COVERS ADJACENT TO OCCUPIED AREAS AS REQUIRED TO CONTAIN DUST AND DEBRIS WITHIN CONSTRUCTION AREA. BROOM CLEAN ALL AREAS, INCLUDING SIDEWALKS AND DRIVEWAYS EACH DAY. KEEP DIRT AND DUST TO A MINIMUM.
- WORK SHALL BE EXECUTED IN A CAREFUL AND ORDERLY MANNER WITH THE LEAST POSSIBLE DISTURBANCE TO PUBLIC AND TO OCCUPANTS OF EXISTING BUILDING.
- CLEAN ALL EXPOSED SURFACES AND NEW EQUIPMENT AFTER COMPLETION.

**APPLICABLE CODES**

ALL WORK PERFORMED UNDER THIS CONTRACT IS TO CONFORM TO THE FOLLOWING CODES AND REGULATIONS:

**2025 CALIFORNIA BUILDING ADMINISTRATIVE CODE**  
PART 1, TITLE 24, CALIFORNIA CODE OF REGULATIONS (CCR)

**2025 CALIFORNIA BUILDING CODE (CBC)**, PART 2, TITLE 24, CCR BASED ON THE 2021 INTERNATIONAL BUILDING CODE (IBC) WITH 2021 CALIFORNIA AMENDMENTS)

**2025 CALIFORNIA ELECTRICAL CODE (CEC)**, PART 3, TITLE 24, CCR BASED ON THE 2020 NATIONAL ELECTRICAL CODE (NEC) WITH 2020 CALIFORNIA AMENDMENTS)

**2025 CALIFORNIA MECHANICAL CODE (CMC)**, PART 4, TITLE 24, CCR BASED ON THE 2021 UNIFORM MECHANICAL CODE (UMC) WITH 2021 CALIFORNIA AMENDMENTS)

**2025 CALIFORNIA PLUMBING CODE (CPC)**, PART 5, TITLE 24, CCR BASED ON THE 2021 UNIFORM PLUMBING CODE (UPC) WITH 2021 CALIFORNIA AMENDMENTS)

**2025 CALIFORNIA ENERGY EFFICIENCY STANDARDS (ENERGY CODE)**, PART 6, TITLE 24 CCR

**2022 SAFETY CODE FOR ELEVATORS AND ESCALATORS**  
(ASME A17.1-2019)

**2025 CALIFORNIA FIRE CODE (CEFC)**, PART 9, TITLE 24, CCR BASED ON THE 2021 INTERNATIONAL FIRE CODE (IFC) WITH 2022 CALIFORNIA AMENDMENTS)

**2025 CALIFORNIA EXISTING BUILDING CODE**, PART 10, TITLE 24 CCR (2021 IEB CODE AND 2022 CALIFORNIA AMENDMENTS)

**2025 CALIFORNIA GREEN BUILDING CODE (CALGreen)**, PART 11, TITLE 24, CCR

**2025 CALIFORNIA REFERENCED STANDARDS**, PART 12, TITLE 24 CCR

**TITLE 19 CCR, PUBLIC SAFETY, STATE FIRE MARSHAL REGULATIONS**

**2010 ADA STANDARDS FOR ACCESSIBLE DESIGN**

NFPA 13 INSTALLATION OF SPRINKLER SYSTEMS 2022 EDITION  
NFPA 14 INSTALLATION OF STANDPIPE SYSTEMS 2019 EDITION  
NFPA 17 STANDARD FOR DRY CHEMICAL EXTINGUISHING SYS. 2021 EDITION  
NFPA 17A STANDARD FOR WET CHEMICAL SYS. 2021 EDITION  
NFPA 20 INSTALLATION OF STATIONARY PUMPS 2019 EDITION  
NFPA 24 INSTALLATION OF PRIVATE FIRE MAINS 2019 EDITION  
NFPA 72 NATIONAL FIRE ALARM AND SIGNALING CODE 2022 EDITION  
NFPA 80 FIRE DOORS AND OTHER OPENING PROTECTIVES 2019 EDITION  
NFPA 92 STANDARD FOR SMOKE CONTROL SYSTEMS 2018 EDITION  
NFPA 253 CRITICAL RADIANT FLUX OF FLOOR COVERING SYS 2018 EDITION  
NFPA 2001 CLEAN AGENT FIRE EXTINGUISHING SYSTEM 2018 EDITION

REFERENCE CODE SECTIONS FOR APPLICABLE STANDARDS - 2025 CBC CHAPTER 35 AND 2025 CFC CHAPTER 45

THE ABOVE CODES AND REGULATIONS REFER TO THE LATEST EDITION OR REVISION IN FORCE ON THE DATE OF THE CONTRACT. UNLESS OTHERWISE STATED, NOTHING ON THE DRAWINGS IS TO BE CONSTRUED AS REQUIRING OR PERMITTING WORK THAT IS CONTRARY TO THE LISTED CODES AND REGULATIONS, OR OTHER LOCAL, STATE OR FEDERAL CODES OR REGULATIONS WHICH MAY BE APPLICABLE.

COMPLIANCE WITH CFC CHAPTER 33, FIRE SAFETY DURING CONSTRUCTION AND DEMOLITION, AND CBC CHAPTER 33, SAFETY DURING CONSTRUCTION WILL BE ENFORCED.

**OWNER**

PLACER COUNTY OFFICES OF EDUCATION  
360 NEVADA ST. TEL: (530) 889-8020  
ALBURN, CA 95603  
CONTACT: MARTIN FREGOSO

**CONSULTANTS**

**ARCHITECT**  
HIBSER YAMAUCHI ARCHITECTS, INC. TEL: (510) 446-2222  
4602 2ND STREET, FAX: (510) 446-2211  
DAVIS, CA 95618  
CONTACT: HOWARD CHO

**MECHANICAL / PLUMBING**  
TURLEY & ASSOCIATES TEL: (916) 325-1065  
2431 CAPITOL AVE  
SACRAMENTO, CA 95816  
CONTACT: NIRAV SHAH

**ELECTRICAL / COMMUNICATIONS**  
M.NEIL'S ENGINEERING INC. TEL: (916) 923-4400  
100 HOWE AVE #205N  
SACRAMENTO, CA 95825  
CONTACT: STUART LINDSAY

**VICINITY MAP** NO SCALE

**SITE / BUILDING INFORMATION**

<b>(E) SITE</b>	
ZONING	B-P/C
PARCEL NO.	APN 017-081-025-000
<b>(E) OFFICE BUILDING</b>	
OCCUPANCY GROUP	A-3 / B
CONSTRUCTION TYPE	III-B
STORIES	TWO-STORY
HEIGHT	43' - 0"
BUILDING AREA	
FIRST FLOOR	34,739 SF
SECOND FLOOR	34,900 SF
TOTAL	69,639 SF
SPRINKLER PROTECTION	YES (WET)
FIRE ALARM SYSTEM	AUTOMATIC
SMOKE CONTROL SYSTEM	NO
RISK CATEGORY	III
PROJECT AREA (TENANT IMPROVEMENTS)	SF

**SCOPE OF WORK**

- REMOVE EXISTING ROOFTOP AIR-HANDLER PACKAGE UNIT (CUSTOM DUAL FAN, DUAL DUCT CHANGEOVER SYSTEM) AND REPLACE IN-KIND.
- A NEW REPLACEMENT UNIT SHALL WEIGH LESS THAN OR EQUAL TO THE UNIT TO BE REMOVED AND SHALL BE SIZED TO FIT OVER THE EXISTING CURB).

**INDEX OF DRAWINGS**

**ARCHITECTURAL**  
A0.01 TITLE SHEET  
A0.02 SYMBOLS, LEGENDS AND ABBREVIATIONS  
A1.01 SITE PLAN

**MECHANICAL**  
M0.01 MECHANICAL LEGENDS, SCHEDULES, NOTES, AND DETAILS  
M3.11 MECHANICAL DEMOLITION ROOF PLAN  
M3.21 MECHANICAL ROOF PLAN


**PLUMBING**  
P0.01 PLUMBING LEGENDS, SCHEDULES, AND NOTES  
P3.11 PLUMBING DEMOLITION ROOF PLAN  
P3.21 PLUMBING ROOF PLAN  
T-24A TITLE 24 REPORTS  
T-24B TITLE 24 REPORTS

**ELECTRICAL**  
E0.01 ELECTRICAL COVER SHEET  
E1.01 SITE PLAN - ELECTRICAL  
E2.10 ROOF PLAN - DEMOLITION - ELECTRICAL  
E2.11 ROOF PLAN - REMODEL - ELECTRICAL

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

This document is the property of the Owner and is not to be used without his written permission.



**HY HIBSER YAMAUCHI Architects, Inc.**  
4602 2nd Street, Suite 3  
Davis, CA 95618  
530.758.1270 tel | 530.758.4789 fax

HY Architects Project number: 6306









Facility  
NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project  
HVAC PACKAGE UNIT REPLACEMENT

Sheet Title  
TITLE SHEET

Client Project Number: N/A

Scale:	Sheet
Drawn By: SHLDLM	<b>A0.01</b>
Checked By: HC	
Issue Date: July 21, 2023	
Revit Version: 2023	
	Sheet of



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY

### ABBREVIATIONS

### SYMBOLS

&	AND	S	SOUTH
@	AT	SC	SOLID CORE
⊕	CENTERLINE	SCD	SEE CIVIL DRAWINGS
⊖	DIAMETER	SCHED	SCHEDULE
#	POUND OR NUMBER	SD	SOAP DISPENSER
A/C	AIR CONDITIONING	SED	SEE ELECTRICAL DRAWINGS
AC	ASPHALTIC CONCRETE	SF	SQUARE FEET
ACOUS	ACOUSTICAL	SFRD	SEE FIRE PROTECTION DRAWINGS
ACT	ACOUSTIC CEILING TILE	SHT	SHEET
ADD	ADDITIONAL	SIM	SIMILAR
ADJ	ADJACENT	SLD	SEE LANDSCAPE DRAWINGS
AF	ABOVE FINISHED FLOOR	SMD	SEE MECHANICAL DRAWINGS
ALT	ALTERNATE	SMS	SHEET METAL SCREW
ALUM	ALUMINIUM	SND	SANITARY NAPKIN DISPENSER
ANOD	ANODIZED	SPD	SEE PLUMBING DRAWINGS
APPROX	APPROXIMATE	SO	SQUARE
ARCH	ARCHITECTURAL	SPEC	SPECIFICATION
BITUM	BITUMINOUS	SS	STAINLESS STEEL
BD	BOARD	SSD	SEE STRUCTURAL DRAWINGS
BLDG	BUILDING	STD	STANDARD
BLKG	BLOCKING	STL	STEEL
BOT	BOTTOM	STOR	STORAGE
BTWN	BETWEEN	STRUCT	STRUCTURAL
BUR	BUILT-UP ROOFING	SUSP	SUSPEND
CAB	CABINET	TEL	TELEPHONE
CB	CATCH BASIN	TEMP	TEMPORARY
CFCI	CONTRACTOR FURNISHED CONTRACTOR INSTALLED	THK	THICK
CG	CORNER GUARD	T.O.	TOP OF
CJ	CONTROL JOINT	TOC	TOP OF CURB
CLG	CEILING	TOP	TOP OF PARAPET
CLO	CLOSET	TOS	TOP OF SLAB
CLR	CLEAR	TOW	TOP OF WALL
CMU	CONCRETE MASONRY UNIT	TPD	TOILET PAPER DISPENSER
CO	CLEAN OUT	TV	TELEVISION
COL	COLUMN	TYP	TYPICAL
COMP	COMPOSITION	UON	UNLESS OTHERWISE NOTED
CONC	CONCRETE	VERT	VINYL COMPOSITION TILE
CONST	CONSTRUCTION	VERT	VERTICAL
CONT	CONTINUOUS	VEST	VESTIBULE
CORR	CORRIDOR	VIF	VERIFY IN FIELD
CT	CERAMIC TILE	W	WEST
CUST	CUSTODIAN	w	WITH
DBL	DOUBLE	w/o	WITHOUT
DEMO	DEMOLITION	WC	WATER CLOSET
DEPT	DEPARTMENT	WD	WOOD
DF	DRINKING FOUNTAIN	WH	WATER HEATER
DI	DRAIN OR DROP INLET		
DIA	DIAMETER		
DIAG	DIAGONAL		
DM	DIMENSION		
DISP	DISPENSER		
DIV	DIVISION		
DN	DOWN		
DS	DOWNSPOUT		
DTL	DETAIL		
DW	DISHWASHER		
DWG	DRAWING		
(E)	EXISTING		
E	EAST		
EA	EACH		
EF	EXHAUST FAN		
EJ	EXPANSION JOINT		
EL	ELEVATION		
ELEC	ELECTRICAL		
ELEV	ELEVATOR		
ENCL	ENCLOSURE		
EQ	EQUAL		
EQUIP	EQUIPMENT		
EVA	EMERGENCY VEHICLE ACCESS		
EW	ELECTRICAL WATER COOLER		
EXP	EXPANSION		
EXT	EXTERIOR		
FA	FIRE ALARM		
FD	FLOOR DRAIN		
FE	FIRE EXTINGUISHER		
FEIC	FIRE EXTINGUISHER CABINET		
FF	FINISH FLOOR		
FIN	FINISH		
FLR	FLOOR		
FO	FACE OF		
FOC	FACE OF CONCRETE		
FOF	FACE OF FINISH		
FOS	FACE OF STUD		
FRP	FIBERGLASS REINFORCED PANEL		
FT	FOOT OR FEET		
FTG	FOOTING		
GA	GALUGE		
GALV	GALVANIZED		
GB	GRAB BAR		
GSM	GALVANIZED WHEET METAL		
GYP	GYPSPUM		
HB	HOSE BIB		
HC	HOLLOW CORE		
HD	HEAD		
HDWR	HARDWARE		
HM	HOLLOW METAL		
HORIZ	HORIZONTAL		
HR	HOUR		
HT	HEIGHT		
INFO	INFORMATION		
INSUL	INSULATION		
INT	INTERIOR		
JAN	JANITOR		
JT	JOINT		
LAB	LABORATORY		
LAM	LAMINATE		
LAV	LAVATORY		
LBS	POUNDS		
LT	LIGHT		
MAX	MAXIMUM		
MB	MACHINE BOLT		
MDF	MEDIUM DENSITY FIREBOARD		
MECH	MECHANICAL		
MFR	MANUFACTURER		
MH	MANNHOLE		
MIN	MINIMUM		
MISC	MISCELLANEOUS		
MOD	MODULAR		
MTD	MOUNTED		
MTG	MOUNTING		
MTL	METAL		
MUL	MULLION		
(N)	NEW		
N/A	NOT APPLICABLE		
N	NORTH		
NIC	NOT IN CONTRACT		
NO or #	NUMBER		
NOM	NOMINAL		
NTS	NOT TO SCALE		
O	OVER		
OC	ON CENTER		
OFCI	OWNER FURNISHED CONTRACTOR INSTALLED		
OFDI	OWNER FURNISHED OWNER INSTALLED		
OPP	OPPOSITE		
PL	PLATE		
PLAM	PLASTIC LAMINATE		
PLAS	PLASTER		
PLYWD	PLYWOOD		
PR	PAIR		
PTD	PAPER TOWEL DISPENSER		
PVC	POLYVINYL CHLORIDE		
(R)	RELOCATE		
RB	RESILIENT OR RUBBER BASE		
ROP	REFLECTED CEILING PLAN		
RD	ROOF DRAIN		
REF	REFERENCE		
REFR	REFRIGERATOR		
REINF	REINFORCED		
REQ	REQUIRED		
RF	RESILIENT FLOORING		
RM	ROOM		
RO	ROUGH OPENING		
RWL	RAIN WATER LEADER		

	GRID LINE
	<b>BUILDING ELEVATION</b> — ELEVATION IDENTIFICATION — SHEET WHERE ELEVATION IS SHOWN
	<b>BUILDING OR WALL SECTION</b> — SECTION IDENTIFICATION — SHEET WHERE SECTION IS SHOWN
	<b>DETAIL</b> — DETAIL IDENTIFICATION — SHEET WHERE DETAIL IS SHOWN
	<b>INTERIOR ELEVATION(S)</b> — DETAIL NO. OF ELEVATION — NO ARROWS MEAN ELEVATION NOT SHOWN — SHEET WHERE ELEVATION IS SHOWN — ELEVATION IDENTIFICATION
	— WORK POINT, CONTROL POINT OR DATUM POINT
	<b>REVISIONS</b> — REVISION NUMBER, SEE REVISION SCHEDULE ON TITLE BLOCK — AREA OF REVISION
	<b>ROOM IDENTIFICATION</b> — ROOM NAME — KAISER ROOM CODE NAME — ROOM NUMBER — CEILING HEIGHT (OTHER THAN EXISTING OR 8'-0" A.F.F.) — 9'-0"
	<b>KEYNOTE TAG</b> — REFER TO KEYNOTE LIST LOCATED ON PLAN SHEETS
	— AREA OF NO WORK
	<b>DOOR TAG (SEE DOOR SCHEDULE)</b> — DOOR MARK — HARDWARE GROUP
	— DOOR MARK
	(E) DOOR TO REMAIN
	(E) DOOR TO BE REMOVED
	(N) DOOR & DOOR FRAME
	<b>WALL TAG</b> — WALL TYPE - REFER TO DRAWING SHEET A9.01
	<b>WINDOW TAG (SEE WINDOW SCHEDULE)</b> — WINDOW MARK
	<b>CASEWORK TAG</b> — CASEWORK TYPE; REFER TO WJ NORTH AMERICAN ARCHITECTURAL WOODWORK & KAISER CASEWORK STANDARDS — CASEWORK DIMENSIONS — CUSTOMIZATIONS & SPECIALTY HARDWARE




Delta	Date	Revisions	By

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

This document is the property of the Owner and is not to be used without his written permission.



**HY HIBSER YAMAUCHI Architects, Inc.**  
4602 2nd Street, Suite 3  
Davis, CA 95618  
530.758.1270 tel | 530.758.4789 fax

HY Architects Project number: 6306







Facility  
NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project  
HVAC PACKAGE UNIT REPLACEMENT

Sheet Title  
SYMBOLS, LEGENDS AND ABBREVIATIONS

Client Project Number: N/A

Scale:	12" = 1'-0"	Sheet	<b>A0.02</b>
Drawn By:	Author		
Checked By:	HC		
Issue Date:	July 21, 2023		
Revit Version:	2023	Sheet of	



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY




Revisions	Delta	Date	Revisions	By

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

This document is the property of the Owner and is not to be used without his written permission.



**HY** HIBSER YAMAUCHI Architects, Inc.  
 4602 2nd Street, Suite 3  
 Davis, CA 95618  
 530.758.1270 tel | 530.758.4789 fax

HY Architects Project number: 6306

Facility  
 NEW MAIN OFFICE  
 1400 STANFORD RANCH, ROCKLIN CA 95765

Project  
 HVAC PACKAGE UNIT REPLACEMENT


Sheet Title  
 SITE PLAN

Client Project Number: N/A

Scale: 1" = 20'-0"  
 Drawn By: LDM/SH  
 Checked By: HC  
 Issue Date: July 21, 2023  
 Revit Version: 2023

Sheet  
**A1.01**  
 Sheet of




2/18/2025 9:27:04 AM C:\Users\WYat\Barr\Documents\6306\_000\_PCOE - 1400 W Stanford Ranch- HVAC Package Unit Replacement\_detailed\_wstarr23.rvt



**1 NONE**  
 1" = 20'-0"



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY



**UNIT MOUNTING DETAIL**  
NO SCALE

### EXISTING MECHANICAL EQUIPMENT SCHEDULE (SHOWN FOR REFERENCE ONLY)

(E) ENERGY LABS CUSTOM DUAL FAN, DUAL DUCT CHANGEOVER SYSTEM. COOLING ONLY SECTION 22,300 CFM @ 2.0 ESP, 46.97 BHP, 50 HP, COOLING ONLY SUPPLY FAN W/ VFD, CAPACITY 160 TONS, SENSIBLE 1,728 MBH. ACCESSORIES: 100% ECONOMIZER, ENERGY RECOVERY HEATWHEEL.

(E) FACTORY HEATING/COOLING SECTION 13,500 CFM @ 1.75 ESP, 18.13 BHP, 20 HP COOLING/HEATING SUPPLY FAN W/ VFD, CAPACITY 50 TONS, SENSIBLE 540 MBH. NATURAL GAS INPUT/OUTPUT 800/600 MBH. ACCESSORIES: EVAPORATIVE CONDENSING, ROOF CURB, SINGLE POINT ELECTRICAL CONNECTION W/ NON-FUSED DISCONNECT. POWER 460V/3Ø/60HZ, MCA 503.1, MOP 600. WEIGHT 50,000 LBS. EER10.7, AFUE 80%. OSA SET TO 10,500 CFM. SMOKE DETECTORS IN SUPPLY AIR FAN SYSTEM.

### NEW MECHANICAL EQUIPMENT SCHEDULE

(N) AIR20 CUSTOM DUAL FAN, DUAL DUCT CHANGEOVER SYSTEM.

COOLING ONLY SECTION 25,000 CFM, COOLING CAPACITY 1242.3 MBH TOTAL/970.4 MBH SENSIBLE. (5) SUPPLY FAN WALL, EC MOTORS, 4.6KW ACTUAL POWER/5.8 KW NOMINAL POWER EACH, 2.0"W.C. ESP/4.34"W.C. TSP. (2) RETURN FAN WALL, EC MOTORS, 3.5KW ACTUAL POWER/4.4 KW NOMINAL POWER EACH, 2.0"W.C. ESP/3.15"W.C. TSP. (2) OUTSIDE AIR FAN WALL, EC MOTORS, 3.4KW ACTUAL POWER/4.2 KW NOMINAL POWER EACH, 1.0"W.C. ESP/2.6"W.C. TSP. (2) DX COILS, 5 ROWS, 11 FPI, 0.471"W.C. AIR PD. (2) SCROLL COMPRESSORS AND (2) DIGITAL COMPRESSORS. REFRIGERANT R454B.

HEATING/COOLING SECTION 13,500 CFM, COOLING CAPACITY 553.5 MBH TOTAL/447.2 MBH SENSIBLE. INDIRECT NATURAL GAS HEATER, 400 MBH INPUT/324 MBH OUTPUT, 5-13.5"W.C. GAS INLET PRESSURE, (3) SUPPLY FAN WALL, EC MOTORS, 4.6KW ACTUAL POWER/5.8 KW NOMINAL POWER EACH, 2.0"W.C. ESP/4.34"W.C. TSP. (2) RETURN FAN WALL, EC MOTORS, 3.5KW ACTUAL POWER/5.0 KW NOMINAL POWER EACH, (1) DX COILS, 8 ROWS, 10 FPI, 0.887"W.C. AIR PD. (1) SCROLL COMPRESSORS AND (1) DIGITAL COMPRESSORS. REFRIGERANT R454B.

92" ENERGY RECOVER WHEEL, 0.178 KW, 0.46" SUPPLY AIR PD, 0.42" RETURN AIR PD.

2.0" MERV 8 PRE-FILTER AND 4.0" MERV 13 POST FILTER.

TOTAL EFFICIENCY: EER/IEER 11.2/12.97, AFUE 81%.

SINGLE POWER CONNECTION, 460V/3Ø/60HZ, FLA 421, MCA 434, MOCP 450.


UNIT OPERATING WEIGHT: 35,000 LBS.

MANUFACTURE PROVIDE AUTOMATED LOGIC CONTROLLER CAPABLE OF BACNET OR MODBUS SERIAL COMMUNICATION, NEW CONTROLLER SHALL BE COMPATIBLE W/ (E)BMS OF THE BUILDING.

CONTRACTOR TO INSTALL DUCT SMOKE DETECTORS AT MAIN SUPPLY DUCT/PLENUM. (1) AT COOLING ONLY BRANCH AND ONE AT HEATING/COOLING SECTION.

### HVAC CONTROLS NOTES:

TEMPERATURE CONTROLS BY AUTOMATED ELECTRIC. CONTACT JEFF LUNA - JLUNA@AUTOMATEDELECTRIC.NET FOR CONTROLS REQUIREMENTS. THE NEW HVAC UNIT TO TIE INTO EXISTING BUILDING MANAGEMENT SYSTEM (BMS). ALL THE EXISTING CONTROL SEQUENCE TO BE MAINTAINED. PROVIDE CONTROLS SUBMITTAL WITH CONTROLS ARCHITECTURE AND SEQUENCE OF OPERATIONS TO MEOR FOR REVIEW AND APPROVAL.



### PLUMBING ABBREVIATIONS

ABV	ABOVE
ABC, OH	ABOVE CEILING, OVERHEAD
AD	ACCESS DOOR
ADA	AMERICANS WITH DISABILITIES ACT
AFF	ABOVE FINISHED FLOOR
BR	BRANCH
CL	CENTERLINE
CO	CLEANOUT
CW	COLD WATER
DIA, Ø	DIAMETER
FC	FLEXIBLE CONNECTION
I.E.	INVERT ELEVATION
(N) (E)	NEW, EXISTING
NIC	NOT IN CONTRACT
POC	POINT OF CONNECTION
(R) (D)	RISE, DROP
RD, OFL	ROOF DRAIN, OVERFLOW
RI	ROUGH-IN
RO	RUN-OUT
SMS	SHEET METAL SCREWS
SOV	SHUT OFF VALVE
TA, FA	TO ABOVE, FROM ABOVE
TB, FB	TO BELOW, FROM BELOW
TBR	TO BE REMOVED
TP	TRAP PRIMER
UG, UF	UNDERGROUND, UNDER FLOOR
UON	UNLESS OTHERWISE NOTED
UTR	UP THROUGH ROOF
V, VR, VTR	VENT, VENT RISER, VENT THRU ROOF
WT	WATERTIGHT
WCO	WALL CLEANOUT

### PIPING MATERIAL SCHEDULE

- WASTE AND VENT PIPE: CONDENSATE DRAINS SHALL BE TYPE L HARD COPPER, WITH LONG SWEEP ELBOWS AND CLEANOUT TEES AT EACH CHANGE IN DIRECTION. CONNECT CONDENSATE DRAINS TO AIR CONDITIONING UNITS WITH P-TRAP AND RUN TO AN APPROVED RECEPTOR AND DRY WELL. PROVIDE VIBRATION ELIMINATORS AT A.C. UNITS.
- GAS PIPE: SCHEDULE 40 BLACK STEEL WITH MALLEABLE IRON SCREWED FITTINGS ABOVE GRADE; WITH CLASS 150 WELDING FITTINGS. CONNECT TO EACH ITEM OF GAS-FIRED EQUIPMENT WITH DRIP LEG AND VALVE. PROVIDE FLEX CONNECTION IN APPROVED SIZES WHERE APPLICABLE. EXTERIOR GAS PIPING TO BE PRIMED AND PAINTED WITH UV PROTECTED PAINT - GRAY COLOR

### APPLICABLE CODES

CODES:


ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE APPLICABLE REGULATIONS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

- STATE OF CALIFORNIA CODE OF REGULATIONS (CCR) TITLE 24, BUILDING STANDARDS: 2025 EDITION OF THE CALIFORNIA BUILDING CODE. 2025 EDITION OF THE CALIFORNIA ELECTRICAL CODE. 2025 EDITION OF THE CALIFORNIA MECHANICAL CODE. 2025 EDITION OF THE CALIFORNIA PLUMBING CODE. 2025 EDITION OF THE CALIFORNIA FIRE CODE.
- NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) LIFE SAFETY CODE, OR.

### COMPLIANCE NOTES

MECHANICAL AND PLUMBING EQUIPMENT SHALL CONFORM TO THE FOLLOWING AS STATED IN THE ENERGY EFFICIENCY STANDARDS, 2025.

- BE CERTIFIED BY THE MANUFACTURER AS COMPLYING WITH THE EFFICIENCY REQUIREMENTS AS PRESCRIBED IN SECTIONS:
  - 110.1 APPLIANCES REGULATED BY THE APPLIANCE EFFICIENCY STANDARDS:
  - 110.2 HVAC EQUIPMENT EFFICIENCY AND PACKAGED CONTROLS:
  - 110.3 SERVICE WATER HEATING EFFICIENCY AND CONTROLS:
  - 110.4 POOL AND SPA HEATING EFFICIENCY AND CONTROLS:
  - 110.5 RESTRICTIONS ON PILOT LIGHTS:
- BE SPECIFIED AND INSTALLED IN ACCORDANCE WITH SECTIONS.
  - 120.1 REQUIREMENTS FOR VENTILATION:
  - 120.2 REQUIRED CONTROLS FOR HVAC SYSTEMS: 102.2 (H) DEMAND SHED CONTROLS.
  - 120.2 (I) ECONOMIZER FAULT DETECTION & DIAGNOSTIC.
  - 120.3 REQUIREMENTS FOR PIPE INSULATION:
  - 120.4 REQUIREMENTS FOR DUCT INSULATION:
  - 120.5 REQUIREMENTS FOR MECHANICAL SYSTEMS
  - 120.8 BUILDING COMMISSIONING
  - 120.9 REQUIREMENTS FOR COMMERCIAL BOILERS



### MECHANICAL ABBREVIATIONS


AAV	AUTOMATIC AIR VENT	MBH	BTU PER HOUR (THOUSAND)
ABV	ABOVE	MC	MECHANICAL CONTRACTOR
ABC, OH	ABOVE CEILING, OVERHEAD	MIN	MINIMUM
AC	AIR CONDITIONING	MPS	MEDIUM PRESSURE STEAM
AD	ACCESS DOOR	(N) (E)	NEW, EXISTING
ADA	AMERICANS W/ DISABILITIES ACT	N.C.	NORMALLY CLOSED
AE	AIR EXTRACTOR	NEG	NEGATIVE
AFF	ABOVE FINISHED FLOOR	NIC	NOT IN CONTRACT
AL	ACOUSTICALLY LINED	N.O.	NORMALLY OPEN
AHU	AIR HANDLING UNIT	OB	OPPOSED BLADE DAMPER
AIP	ABANDON IN PLACE	OC	ON CENTER
APD	AIR PRESSURE DROP	OP	OPERATING
BHP	BRAKE HORSEPOWER	PH	PHASE
BOD	BOTTOM OF DUCT	POC	POINT OF CONNECTION
BR	BRANCH	PSI	POUNDS PER SQUARE INCH
BTU	BRITISH THERMAL UNIT	PT	PRESSURE TREATED
BTUH	BTU PER HOUR	PTDF	PRESSURE TREATED DOUGLAS FIR
CAV	CONSTANT AIR VOLUME	P&TRV	PRESSURE & TEMPERATURE RELIEF VALVE
CD	CONDENSATE DRAIN	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
CFM, f	CUBIC FEET OF AIR PER MINUTE	(R) (D)	RISE, DROP
CFPS	CUBIC FEET PER SECOND	RD, OFL	ROOF DRAIN, OVERFLOW
CL	CENTERLINE	REF	ROOF EXHAUST FAN
CO	CLEANOUT	REQ'D	REQUIRED
CONC.	CONCRETE	RL	REFRIGERANT LIQUID
CONN.	CONNECT	RPM	REVOLUTIONS PER MINUTE
CR	CONDENSATE RETURN (STEAM)	RS	REFRIGERANT SUCTION
CS	CURRENT SENSOR	SAD	SEE ARCHITECTURAL DRAWINGS
CU	CONDENSING UNIT	SED	SEE ELECTRICAL DRAWINGS
CU FT	CUBIC FEET	SM	SHEET METAL
CU IN	CUBIC INCHES	SMS	SHEET METAL SCREWS
CWB	CONSTANT VOLUME BOX	SOV	SHUT OFF VALVE
CV	COLD WATER	SS	STAINLESS STEEL
DB	DRY BULB	SSD	SEE STRUCTURAL DRAWING
DF	DOUGLAS FIR	STL	STEEL
DIA, Ø	DIAMETER	TA, FA	TO ABOVE, FROM ABOVE
DSP	DUCT STATIC PRESSURE SENSOR	TB, FB	TO BELOW, FROM BELOW
EA, OA, RA, SA	EXHAUST, OUTSIDE, RETURN & SUPPLY AIR	TBR	TO BE REMOVED
E.C.	ELECTRICAL CONTRACTOR	TCC	TEMPERATURE CONTROL CONTRACTOR
ESP	EXTERNAL STATIC PRESSURE	TCP	TEMPERATURE CONTROL PANEL
EWT	ENTERING WATER TEMPERATURE	THK	THICK
FA	FACE AREA (SQUARE FEET)	TR	TO REMAIN
FC	FLEXIBLE CONNECTION	TSP	TOTAL STATIC PRESSURE
FLA	FULL LOAD AMPS	TV	TURNING VANES
FPI	FPI'S PER INCH	TYP	TYPICAL
FBM	FEET PER MINUTE	UG, UF	UNDERGROUND, UNDER FLOOR
GALV.	GALVANIZED	UON	UNLESS OTHERWISE NOTED
GA	GAUGE	UTR	UP THROUGH ROOF
GC	GENERAL CONTRACTOR	VAC	VOLTS ALTERNATING CURRENT
GSM	GALVANIZED SHEET METAL	VFD	VARIABLE FREQUENCY DRIVE
HP	HORSE POWER	VIF	VERIFY IN FIELD
HWS	HOT WATER SUPPLY	WB	WET BULB
HWR	HOT WATER RETURN	WG	WATER GAUGE
HZ	FREQUENCY (HERTZ)	WOG	WATER OIL GAS PRESSURE RATING
LBS	POUNDS	WP	WATER PRESSURE
LRA	LOCKED ROTOR AMPS	WPD	WATER PRESSURE DROP
LWT	LEAVING WATER TEMPERATURE	WT, AT	WATERTIGHT, AIRTIGHT
MAV	MANUAL AIR VENT		
MAX	MAXIMUM		



Revisions	Delta	Date	Revisions	By

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL



Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project: HVAC PACKAGE UNIT REPLACEMENT

Sheet Title: MECHANICAL LEGENDS, SCHEDULES, NOTES, AND DETAILS

Client Project Number: N/A









Scale: As indicated

Drawn By: T&A

Checked By: T&A

Issue Date: JANUARY 30, 2026


Sheet of: M0.01



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY




Revisions			
Delta	Date	Revisions	By



(E)AC-1  
TR. DISCONNECT  
DUCTWORK, PIPING  
AND CONTROL  
WIRING AND FIRE  
ALARM WIRING.  
(E)CURB TO REMAIN  
FIELD VERIFY  
(E)CURB  
DIMENSIONS AND  
CONDITION. PROVIDE  
NECESSARY REPAIR  
OF (E)CURB

**DEMOLITION  
MECHANICAL ROOF PLAN**

SCALE: 3/32" = 1'-0"



**PREMEASUREMENT NOTES**

PRIOR TO SHUT DOWN AND DEMOLITION (E)AC-1, PREMEASUREMENT FOLLOWING PARAMETERS OF (E)AC-1:

**COLD TUNNEL:**

TOTAL SUPPLY AND RETURN AIRFLOW; SUPPLY AND RETURN STATIC PRESSURE;

**HOT/COLD TUNNEL:**

TOTAL SUPPLY AND RETURN AIRFLOW; SUPPLY AND RETURN STATIC PRESSURE;

**MIN/MAX OUTSIDE AIR FLOWS**



WHEN DOING THE AIRFLOW MEASUREMENT, ALL VAV BOXES SERVING BY THE SYSTEM SHALL WORK UNDER MAX COOLING MODE (MAX AIRFLOW).

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

<b>TURLEY MECHANICAL &amp; ASSOCIATES</b>		<b>ENGINEERING</b>	
1100 Cassaba Oaks Drive San Jose, CA 95033		(916) 225-5886 Fax: (916) 225-9005 Email: <a href="mailto:office@turley.com">office@turley.com</a>	
Project Engineer:	MS	Job Number:	20224
Project Manager:	MS	Proj. Date:	Jan 28, 2026 - 4/1/26
Project Number:	221	Logic:	40000

This document is the property of the Owner and is not to be used without his written permission



4602 2nd Street, Suite 3  
Davis, CA 95618  
530.758.1270 tel; 530.758.4789 fax









Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project: HVAC PACKAGE UNIT REPLACEMENT

Sheet Title: MECHANICAL DEMOLITION ROOF PLAN

Client Project Number: N/A


Scale:	As indicated	Sheet	<b>M3.11</b>
Drawn By:	T&A		
Checked By:	T&A		
Issue Date:	JANUARY 30, 2026	Sheet of	




IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY



Revisions			
Delta	Date	Revisions	By



**A** MECHANICAL ROOF PLAN  
SCALE: 3/32" = 1'-0"



- KEY NOTES**
- ◇ PROVIDE NECESSARY DUCT OFFSET, FITTING, AND FLEXIBLE CONNECTOR TO CONNECT (E)DUCTWORK TO (N)UNIT AT THE BOTTOM.
  - ◇ WHEN (N)UNIT INSTALLED, RECONNECT DUCTWORK, CONTROL WIRING AND FIRE ALARM WIRING TO (E)SYSTEMS. DRAIN PIPING CONNECTION SEE PLUMBING DRAWINGS.



- GENERAL NOTES**
- AFTER INSTALLATION, BALANCE SUPPLY/RETURN AIRFLOW OF COLD TUNNEL AND HOT/COLD TUNNEL TO PREMEASURED VALUES. SET OUTSIDE AIRFLOW TO PREMEASURED VALUES.

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

<b>TURLEY MECHANICAL &amp; ASSOCIATES</b>		<b>MECHANICAL ENGINEERS</b>	
1100 Cassaba Oaks Drive San Jose, CA 95088		(916) 225-5866 Fax: (916) 225-9005 Email: <a href="mailto:office@turley.com">office@turley.com</a>	
Project Engineer:	MS	Job Number:	20224
Project Manager:	MS	Proj. Date:	Jan 28, 2026 - 4:15pm
Project Designer:	MS	Logic:	ASAP

This document is the property of the Owner and is not to be used without his written permission











Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765


Project: HVAC PACKAGE UNIT REPLACEMENT

Sheet Title: MECHANICAL ROOF PLAN

Client Project Number:	N/A
Scale:	As indicated
Drawn By:	T&A
Checked By:	T&A
Issue Date:	JANUARY 30, 2026
Sheet	M3.21
Sheet	of



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY



NOTE:  
 1. APPLICABLE FOR CONDENSATE PIPING TO RTU UNITS. ALL CONDENSATE PIPE SHALL BE TYPE L COPPER AND SLOPE MIN. OF 1/8\"/>

**C** PIPE SUPPORT ON ROOF DETAIL  
NO SCALE

### COMPLIANCE NOTES

MECHANICAL AND PLUMBING EQUIPMENT SHALL CONFORM TO THE FOLLOWING AS STATED IN THE ENERGY EFFICIENCY STANDARDS, 2025.

- BE CERTIFIED BY THE MANUFACTURER AS COMPLYING WITH THE EFFICIENCY REQUIREMENTS AS PRESCRIBED IN SECTIONS:
  - 110.1 APPLIANCES REGULATED BY THE APPLIANCE EFFICIENCY STANDARDS;
  - 110.2 HVAC EQUIPMENT EFFICIENCY AND PACKAGED CONTROLS;
  - 110.3 SERVICE WATER HEATING EFFICIENCY AND CONTROLS;
  - 110.4 POOL AND SPA HEATING EFFICIENCY AND CONTROLS;
  - 110.5 RESTRICTIONS ON PILOT LIGHTS;
- BE SPECIFIED AND INSTALLED IN ACCORDANCE WITH SECTIONS.
  - 120.1 REQUIREMENTS FOR VENTILATION;
  - 120.2 REQUIRED CONTROLS FOR HVAC SYSTEMS:
    - 102.2 (H) DEMAND SHED CONTROLS;
    - 120.2 (I) ECONOMIZER FAULT DETECTION & DIAGNOSTIC;
  - 120.3 REQUIREMENTS FOR PIPE INSULATION;
  - 120.4 REQUIREMENTS FOR DUCT INSULATION;
  - 120.5 REQUIREMENTS FOR MECHANICAL SYSTEMS;
  - 120.8 BUILDING COMMISSIONING;
  - 120.9 REQUIREMENTS FOR COMMERCIAL BOILERS;



### APPLICABLE CODES

ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE APPLICABLE REGULATIONS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:


A) STATE OF CALIFORNIA CODE OF REGULATIONS (CCR) TITLE 24.

2025 EDITION OF THE CALIFORNIA BUILDING CODE.  
 2025 EDITION OF THE CALIFORNIA ELECTRICAL CODE.  
 2025 EDITION OF THE CALIFORNIA FIRE CODE.  
 2025 EDITION OF THE CALIFORNIA MECHANICAL CODE.  
 2025 EDITION OF THE CALIFORNIA PLUMBING CODE.

B) NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) LIFE SAFETY CODE.



**A** CONDENSATE DRAIN P-TRAP AT AC  
NO SCALE



**B** EQUIPMENT GAS CONNECTION DETAIL  
NO SCALE

### PLUMBING LEGEND

	COLD WATER LINE
	CONDENSATE DRAIN
	FIRE SERVICE LINE
	GAS
	HOT WATER LINE
	HOT WATER RETURN
	LIQUID PETROLEUM GAS
	OVERFLOW
	PIPING OR EQUIPMENT TO BE REMOVED
	RAINWATER LEADER
	RISE OR DROP IN DIRECTION OF FLOW
	SANITARY SOIL OR WASTE LINE
	SECONDARY CONDENSATE DRAIN LINE
	TRAP PRIMER LINE
	VENT
	CLEANOUT & WALL CLEANOUT
	FIRE DEPARTMENT CONNECTION
	FLOOR/ GRADE CLEAN OUT
	FLOOR DRAIN
	HOSE BIBB/ WALL HYDRANT
	TRAP
	TRAP PRIMER
	BALANCING VALVE
	BALL VALVE
	BUTTERFLY VALVE
	CHECK VALVE
	FLEXIBLE CONNECTION
	GATE VALVE
	SHUT OFF COCK
	PRESSURE GAUGE
	PRESSURE REDUCING VALVE
	REDUCER
	PRESSURE & TEMPERATURE RELIEF VALVE
	SHUT OFF VALVE
	STRAINER
	STRAINER & DRAIN VALVE WITH HOSE FITTING
	SOLENOID VALVE
	THERMOMETER
	UNION

### PLUMBING ABBREVIATIONS

ABV	ABOVE
ABC, OH	ABOVE CEILING, OVERHEAD
AD	ACCESS DOOR
ADA	AMERICANS WITH DISABILITIES ACT
AFF	ABOVE FINISHED FLOOR
AIP	ABANDON IN PLACE
BR	BRANCH
CL	CENTERLINE
CO	CLEANOUT
CW	COLD WATER
DHW	DOMESTIC HOT WATER
DHWR	DOMESTIC HOT WATER RETURN
DIA, Ø	DIAMETER
FC	FLEXIBLE CONNECTION
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FSR	FIRE SPRINKLER RISER
GCO	GRADE CLEANOUT
HW	HOT WATER
HWR	HOT WATER RETURN
I.E.	INVERT ELEVATION
(N) (E)	NEW, EXISTING
NIC	NOT IN CONTRACT
POC	POINT OF CONNECTION
P, TRV	PRESSURE & TEMPERATURE RELIEF VALVE
RPPB	REDUCED PRESSURE BACKFLOW PREVENTER
(R) (D)	RISE, DROP
RD, OFL	ROOF DRAIN, OVERFLOW
RI	ROUGH-IN
RO	RUN-OUT
SMS	SHEET METAL SCREWS
SOV	SHUT OFF VALVE
TA, FA	TO ABOVE, FROM ABOVE
TB, FB	TO BELOW, FROM BELOW
TBR	TO BE REMOVED
TP	TRAP PRIMER
UG, UF	UNDERGROUND, UNDERFLOOR
UON	UNLESS OTHERWISE NOTED
UTR	UP THROUGH ROOF
V, VR, VTR	VENT, VENT RISER, VENT THRU ROOF
WT	WATERTIGHT
WCO	WALL CLEANOUT

### PIPING MATERIAL SCHEDULE

SYSTEM	LOCATION	MATERIAL		MATERIAL	
		MATERIAL	TEST METHOD	MATERIAL	TEST METHOD
CONDENSATE DRAIN	ABOVE SLAB	TYPE "M" HARD TEMPER SEAMLESS COPPER	ASTM B88	WROUGHT COPPER FITTINGS WITH 95/5 TIN-SILVER SOLDERED JOINTS	ANSI B16.22
GAS PIPE	ABOVE SLAB	SCHEDULE 40 BLACK STEEL*	ASTM A53	MALLEABLE IRON THREADED FITTINGS CLASS 150#	ASME B16.3




\* PRIME & PAINT ALL OUTDOOR GAS PIPING w/UV PROTECTED PAINT (GRAY).



Delta	Date	Revisions	By

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL



Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project: HVAC PACKAGE UNIT REPLACEMENT









Sheet Title: PLUMBING LEGENDS, SCHEDULES, AND NOTES

Client Project Number: N/A

Scale: As Indicated  
 Drawn By: T&A  
 Checked By: T&A  
 Issue Date: JANUARY 30, 2026

**P0.01**


Sheet of




IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY



Revisions			
Delta	Date	Revisions	By



**A** DEMOLITION PLUMBING ROOF PLAN  
SCALE: 3/32" = 1'-0"



**B** PARTIAL ENLARGED DEMOLITION PLUMBING 2ND FLOOR PLAN  
SCALE: 3/16" = 1'-0"

CONSTRUCTION DOCUMENTS  
AGENCY APPROVAL

<b>TURLEY MECHANICAL &amp; ASSOCIATES</b>	
1700 Chesapeake Oaks Drive Suite 100 Saratoga, CA 95088	(916) 225-5886 Fax: (916) 225-9000 Email: <a href="mailto:office@turley.com">office@turley.com</a>
Project Engineer: MS	Job Number: 20224
Project Manager: MS	Proj. Date: Jan 28, 2026 - 4:15pm
Project Number: 221	Logic: 40248

This document is the property of the Owner and is not to be used without his written permission.











**HY HIBSER YAMAUCHI Architects, Inc.**  
4602 2nd Street, Suite 3  
Davis, CA 95618  
530.758.1270 tel | 530.758.4789 fax

Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project: HVAC PACKAGE UNIT REPLACEMENT

Sheet Title: PLUMBING DEMOLITION ROOF PLAN


Client Project Number: N/A	Sheet
Scale: As indicated	<b>P3.11</b>
Drawn By: T&A	
Checked By: T&A	
Issue Date: JANUARY 30, 2026	
Sheet of	




IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY



Delta	Date	Revisions	By



**A PLUMBING ROOF PLAN**  
SCALE: 3/32" = 1'-0"




- KEY NOTES**
- ◆ (N)1 1/4"CD FROM DX COILS. PROVIDE P-TRAP AND CLEAN-OUT. SEE A/P0.01.
  - ◆ (N)1 1/4"CD ON ROOF SHALL HAVE MIN 1/8" FEET SLOPE TOWARD FLOW DIRECTION.
  - ◆ (N)3/4" DRAIN FROM INDIRECT BURNER. (N)3/4" DRAIN ON ROOF SHALL HAVE MIN 1/8" FEET SLOPE TOWARD FLOW DIRECTION.
  - ◆ (N)2 1/2" G CONNECT TO (N)AHU. SEE B/P0.01.

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

<b>TURLEY MECHANICAL &amp; ASSOCIATES</b>	
1100 Cassaba Oaks Drive Suite 100 Sacramento, CA 95833	(916) 225-5986 Fax: (916) 225-5985 Email: <a href="mailto:office@turley.com">office@turley.com</a>
Project Engineer: MS	Job Number: 20224
Project Manager: MS	Proj Date: Jan 28, 2026 - 4:15pm
Project Number: 221	Logic: 40248

This document is the property of the Owner and is not to be used without his written permission










Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project: HVAC PACKAGE UNIT REPLACEMENT

Sheet Title: PLUMBING ROOF PLAN

Client Project Number:	N/A
Scale:	As indicated
Drawn By:	T&A
Checked By:	T&A
Issue Date:	JANUARY 30, 2026
Sheet	<b>P3.21</b>
Sheet of	



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY




Delta	Date	Revisions	By

**CONSTRUCTION DOCUMENTS**

**AGENCY APPROVAL**

**TURLEY & ASSOCIATES** MECHANICAL ENGINEERS  
 1100 Quailside Oaks Drive, Suite 100, San Ramon, CA 94583  
 (916) 255-5566 Fax: (916) 255-5566  
 Email: ct@tdaengineers.com

Project Engineer: NS Job Number: 25236  
 Project Manager: NS Exp: 6/30/22  
 Project Designer: NS License: 2025-10-03-24



**HIBSER YAMAUCHI ARCHITECTS, INC.**  
 4602 2nd Street, Suite 3  
 Davis, CA 95618  
 530.758.1270 Int | 530.758.4789 Fax

HY Architects Project number: 6306

Facility  
**HVAC PACKAGE UNIT REPLACEMENT**

Sheet Title  
**TITLE-24 REPORTS**

Client Project Number: N/A  
 Scale: As indicated Sheet  
 Drawn By: T&A  
 Checked By: T&A  
 Issue Date: JANUARY 30, 2026  
**T-24A**  
 Sheet of

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 7 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**I. SYSTEM CONTROLS**  
 This table is used to demonstrate compliance with mandatory controls in §110.2 and §120.2 and prescriptive controls in §140.4(f) and (n), §170.2(c)(4) or requirements in §141.0(b)(2) or §180.2(b)(2) for altered space conditioning systems.

01	02	03	04	05	06	07	08	09	10	11
System Name	System Zoning	Conditioned Floor Area Being Served (ft <sup>2</sup> )	Thermostats §110.2(b) & (c), §120.2(a) or §160.3(a)(2A) or §160.3(b)(8) or §141.0(b)(2)E & §180.2(b)(2)	Shut-Off Controls §120.2(e) & §160.3(a) 2D	Isolation Zone Controls §120.2(g) & §170.2(c) 4D	Demand Response §110.12 §120.2(b) & §160.3(a)(2)B	Supply Air Temp. Reset §140.4(f) & §170.2(c) 4D	Window Interlocks per §140.4(n) & §170.2(c)(4)D	Direct Digital Control (DDC) per §120.2	Heat Pump Defrost per §160.3(b)(7)
(NJAC-1)	Multi-zone w/ DDC to zone	NA: Altered per §141.0(b)(2)E	EMCS	EMCS	EMCS	EMCS	NA: Alteration	NA: Alteration Project	DDC controller logic using ASHRAE Guideline 36	NA: Altered Equipment

<sup>1</sup> FOOTNOTES: Gravity gas wall heaters, gravity floor heaters, gravity room heaters, non-central electric heaters, fireplaces or decorative gas appliances, wood stoves are not required to have setback thermostats.

**J. VENTILATION AND INDOOR AIR QUALITY**  
 This section does not apply to this project.

**K. TERMINAL BOX CONTROLS**  
 This section does not apply to this project.

**L. DISTRIBUTION (DUCTWORK AND PIPING)**  
 This section does not apply to this project.

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 8 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**M. COOLING TOWERS**  
 This section does not apply to this project.

**N. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION**  
 Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at <https://www.energy.ca.gov/programs-and-topics/programs/building-energy-efficiency-standards/2022-building-energy-efficiency-4>

Form/Title  
 NRCC-MCH-E - Must be submitted for all buildings

**O. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE**  
 Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at <https://www.energy.ca.gov/programs-and-topics/programs/building-energy-efficiency-standards/2022-building-energy-efficiency-4>

Form/Title	Systems/Spaces To Be Field Verified
NRCA-MCH-05-A - Air Economizer, DOAS, HRV, & ERV Controls	(NJAC-1)
NRCA-MCH-07-A Supply Fan Variable Flow Controls	(NJAC-1 Supply Fan 1; NJAC-1 Supply Fan 2)
NRCA-MCH-11-A Automatic Demand Shed Controls	(NJAC-1)
NRCA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance	(NJAC-1)
NRCA-MCH-18-A Energy Management Control Systems	(NJAC-1)

**P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION**  
 There are no NRCV forms required for this project.

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 4 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)**  
**Mechanical Heat Recovery §140.4(s)**

01	02	03	04	05	06	07
Name or Item Tag	Coincident Peak Cooling Load of All High Load Spaces (kBtu/h)	Design Capacity of All Mechanical Cooling Systems <sup>2</sup> (kBtu/h)	Design Capacity of All Service Water Heating Systems <sup>1</sup> (kBtu/h)	Design Capacity for all space heating systems (kBtu/h)	Simultaneous Mechanical Heat Recovery	
(NJAC-1)	1,272.7	1,795.8	0	648	Not Required	

<sup>1</sup> FOOTNOTES: Excluding systems expected to operate less than 5 hours per week.  
<sup>2</sup> FOOTNOTES: If the design includes capacity for future cooling systems, then assume 20% of future systems serve high load spaces.

**G. PUMPS**  
 This section does not apply to this project.

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 5 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**H. FAN SYSTEMS & AIR ECONOMIZERS**  
 This table is used to demonstrate compliance with prescriptive requirements found in §140.4(c), §140.4(e), §140.4(f), §170.2(c)(3), and §170.2(c)(4A) for fan systems. Fan systems serving only process loads are exempt from these requirements and do not need to be included in Table H.

System Name	(NJAC-1)	Quantity	Fan System Status	Alteration	System Zoning	Multi-zone VAV systems	Serving Dwelling Units	Not Serving Dwelling Units	Fan System Airflow (cfm)	38,500	Site Elevation	249	Economizer	Differential Temperature
01	02	03	04	05	06	07	08	09	10	11				
Fan Name or Item Tag	Fan Type	Qty	Component	Airflow through Component (%)	Water Gauge (w.g.)	Component Allowance (watt/cfm)	Fan Allowance (watt/cfm) <sup>1</sup>	Design Electrical Input Power Method	Motor Nameplate Horsepower	Fan Electrical Input Power (kW)				
(NJAC-1) Supply Fan 1	Supply	5	Hydronic/DX cooling coil or heat pump coil	100		0.105	0.21	Manufacturer provided		4.6				
(NJAC-1) Supply Fan 2	Supply	3	Altered: Supply Fan System	100		0.105	0.105	Manufacturer provided		4.6				
(NJAC-1) Return Fan 1	Return	2	Altered: Exhaust/Relief/Return/Transfer Fan System	100			0.054	Manufacturer provided		3.5				
Supply Fan Base Allowance (watt/cfm)	0.413		Exhaust/Return/Relief/Transfer Fan Base Allowance (watt/cfm)	0.23		Fan System Allowance (kW) <sup>3</sup>	81.69	Fan System Electrical Input Power (kW)		43.8				

<sup>1</sup> FOOTNOTES: Fans serving spaces with design background noise goals below NC35  
<sup>2</sup> Low-turndown single-zone VAV fan system must be capable of and configured to reduce airflow to 50 percent of design airflow and use no more than 30 percent of the design wattage at that airflow. No more than 10 percent of the design load served by the equipment shall have fixed loads.  
<sup>3</sup> Fan system allowance includes fan system base allowance.  
<sup>4</sup> Filter pressure loss can only be counted once per fan system.

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 6 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**H. FAN SYSTEMS & AIR ECONOMIZERS**  
<sup>3</sup> Complex Fan System means a fan system that combines a single cabinet fan system with other supply fans, exhaust fans, or both.  
<sup>4</sup> Computer room economizers must meet requirements of §140.9(a) and will be documented on the NRCC-PRC-E document.  
<sup>5</sup> Indoor fans meeting the requirements of 140.4(a)(3) shall turn off when there is no demand for heating or cooling in the space. At 66% air flow the power draw shall be no more than 51% of the fan power at full fan speed and at 33% airflow the power draw shall be no more than 12% of the fan power at full fan speed.

**H. EXHAUST AIR HEAT RECOVERY §140.4(q), §170.2(c)(4)**

01	02	03	04	05	06	07	08	09	10	11
Fan System Name	Qty	Hours of Operation per Year	Design Supply Airflow Rate	Outdoor Airflow	% Outdoor Air at Full Design Airflow	Exemptions to Exhaust Air Heat Recovery Requirement per §140.4(q) & §170.2(c)(4)	Exhaust Air Heat Recovery §140.4(q) & §170.2(c)(4)	Type of Heat Recovery Rating	Required Recovery Ratio	Energy Recovery Bypass
(NJAC-1)	1	< 8,000	38,500	10,500	27	No Exemptions Apply	Required for heating and cooling design conditions	Sensible Energy Recovery Ratio	0.6	Economizer Controls per §140.4(q)(2)

**Fan Energy Index (FEI)**

01	02	03
Name or Item Tag	FEI Exception	FEI
(NJAC-1)	Altered Fan System	

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 1 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**A. GENERAL INFORMATION**

01 Project Location (city)	Rocklin	04 Total Conditioned Floor Area	57860
02 Climate Zone	11	05 Total Unconditioned Floor Area	0
03 Occupancy Types Within Project:		06 # of Stories (Habitable Above Grade)	2

Office

**B. PROJECT SCOPE**  
 This table includes mechanical systems or components that are within the scope of the permit application and are demonstrating compliance using the prescriptive path outlined in §140.4, §170.2(b) or §141.0(b)(2) and §180.2(b)(2) for alterations.

01	02	03
Air System(s)	Wet System Components	Dry System Components
<input checked="" type="checkbox"/> Heating Air System	<input type="checkbox"/> Water Economizer	<input checked="" type="checkbox"/> Air Economizer
<input checked="" type="checkbox"/> Cooling Air System	<input type="checkbox"/> Pumps	<input type="checkbox"/> Electric Resistance Heat
<input type="checkbox"/> Ventilation (including DOAS, ERV, HRV systems)	<input type="checkbox"/> System Piping	<input checked="" type="checkbox"/> Fan Systems
	<input type="checkbox"/> Cooling Towers	<input type="checkbox"/> Ductwork (existing to remain, altered or new)
Mechanical Controls	<input type="checkbox"/> Chillers	
<input checked="" type="checkbox"/> Mechanical Controls (existing to remain, altered or new)	<input type="checkbox"/> Boilers	<input type="checkbox"/> Zonal Systems/ Terminal Boxes

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 2 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**C. COMPLIANCE RESULTS**  
 Table C will indicate if the project data input into the compliance document is compliant with mechanical requirements. This table is not editable by the user. If this table says "DOES NOT COMPLY" or "COMPLIES with Exceptional Conditions" refer to Table D, or the table indicated as not compliant for guidance.

01	02	03	04	05	06	07	08	09							
System Summary §110.1, §110.2, §140.4, §170.2(c), §141.0(b), §180.2(b)(2)	AND	Pumps §170.2(c)(4)	AND	Fans/Economizers §140.4(c), §140.4(e), §140.4(p), §170.2(c)	AND	System Controls §120.2, §140.4(f), §140.4(i), §170.2(c)	AND	Ventilation §120.1, §160.2	AND	Terminal Box Controls §140.4(d), §170.2(c)(4)B	AND	Distribution §120.3, §140.4(i), §160.2, §160.3, §141.0(b)(2)D, §180.2(b)(2)(i)	AND	Cooling Towers §110.2(e)(2)	COMPLIES
(See Table F)		(See Table G)		(See Table H)		(See Table I)		(See Table J)		(See Table K)		(See Table L)		(See Table M)	
Yes	AND	Yes	AND	Yes	AND	Yes	AND	Yes	AND	Yes	AND	Yes	AND	Yes	COMPLIES

**Mandatory Measures Compliance (See Table Q for Details)** COMPLIES

**D. EXCEPTIONAL CONDITIONS**  
 This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

**E. ADDITIONAL REMARKS**  
 This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

**F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)**  
**Space Conditioning System Information**

01	02	03	04	05	06
System Name	Quantity	System Serving	System Status	Space Type	Utilizing Recovered Heat
(NJAC-1)	1	Multi-zone	Alteration	Office	<input checked="" type="checkbox"/>

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
**CERTIFICATE OF COMPLIANCE** NRCC-MCH-E  
 Project Name: 25236 - PCOE Report Page: (Page 3 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)**  
**Dry System Equipment Sizing (includes air conditioners, condensers, heat pumps, VRF, furnaces and unit heaters and DOAS systems)**









01	02	03	04	05	06	07	08	09	10	11
Name or Item Tag	Equipment Category per Tables 110.2, §140.4(a)(2) and §170.2(c)(3a)	Equipment Type per Tables 110.2 and Title 20	Smallest Size Available <sup>1</sup> §140.4(a) and §170.2(c)(1)	Per Design (kBtu/h)	Rated (kBtu/h)	Supp. Heating Output (kBtu/h)	Sensible Per Design (kBtu/h)	Rated (kBtu/h)	Total Heating Load (kBtu/h)	Total Sensible Cooling Load (kBtu/h)
(NJAC-1)	Furnace + AC (split or packaged)	AC, air cooled, single pkg + warm-air central furnace, gas-fired	Yes	648	648	0	1,417.6	1,796.1	625	1,103.8

<sup>1</sup> FOOTNOTES: Equipment shall be the smallest size within the available options of the desired equipment line, necessary to meet the design heating and cooling loads of the building per §140.4(a) and §170.2(c)(1). Healthcare facilities are exempted.  
<sup>2</sup> It is common practice to show rated output capacity on the equipment schedule. Sensible cooling output comes from specification sheet tables.  
<sup>3</sup> If equipment is heating only, leave cooling output and load blank. If equipment is cooling only, leave heating output and load blank.  
<sup>4</sup> Authority Having Jurisdiction may ask for load calculations used for compliance per §140.4(b) and §170.2(c).

**Dry System Equipment Efficiency (other than Package Terminal Air Conditioners (PTAC) and Package Terminal Heat Pumps (PTHP), DX-DOAS and Dual Fuel Heat Pumps)**

01	02	03	04	05	06	07	08	09	10
Name or Item Tag	Size Category (Btu/h)	Rating Condition (°F)	Efficiency Unit	Design Efficiency	Refrigerant Loop Heat Recovery	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Title 20	Design Efficiency	Minimum Efficiency Required per Tables 110.2 / Title 20
(NJAC-1)	>=760Btu/h cooling/ >=22548Btu/h heating		TE	0.8	0.8	EER	9.5	10.7	12.3

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
 CERTIFICATE OF COMPLIANCE NRCC-MCH-4  
 Project Name: 25236 - PCOE Report Page: (Page 9 of 10)  
 Date Prepared: 2026-01-29T13:55:36-05:00

**Q. MANDATORY MEASURES DOCUMENTATION LOCATION**  
 This table is used to indicate where mandatory measures are documented in the plan set or construction documentation.

D1		D2	
Compliance with Mandatory Measures documented through MCH		Plan sheet or construction document location	
Mandatory Measures Note Block	No		
D3		D4	
Mandatory Measure		Plan sheet or construction document location	
Heating Equipment Efficiency per §110.1, Title 20, and federal minimums		MD.01	
Cooling Equipment Efficiency per §110.1, Title 20, and federal minimums		MD.01	
Furnace Standby Loss Control per §110.2(d)		N/A	
Heat Pump with Supplemental electric Resistance Heater Controls per §110.2(b)		N/A	

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44

STATE OF CALIFORNIA  
**Mechanical Systems** CALIFORNIA ENERGY COMMISSION  
 CERTIFICATE OF COMPLIANCE NRCC-MCH-4  
 Project Name: 25236 - PCOE Report Page: (Page 10 of 10)  
 Project Address: 1400 Stanford Ranch, Rocklin CA 95765 Date Prepared: 2026-01-29T13:55:36-05:00

**DOCUMENTATION AUTHOR'S DECLARATION STATEMENT**  
 I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Austin Hoang	Documentation Author Signature: <i>Austin</i>
Company: Turley & Associates	Signature Date: 2026-01-29
Address: 1760 Creekside Oaks Drive, Suite 120	CEAA/EA/ECC Certification Identification (if applicable):
City/State/Zip: Sacramento CA 95833	Phone:

- RESPONSIBLE PERSON'S DECLARATION STATEMENT**  
 I certify the following under penalty of perjury, under the laws of the State of California:
- The information provided on this Certificate of Compliance is true and correct.
  - I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).
  - The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
  - The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.
  - I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.

Responsible Person Name: Nirav Shah	Responsible Person Signature: <i>Nirav</i>
Responsible Person Scope: Mechanical Designer	Date Signed: 2026-01-29
Company: Turley & Associates	License: M40257
Address: 1760 Creekside Oaks Drive, Suite 120	Phone:
City/State/Zip: Sacramento CA 95833	

Generated Date/Time: Documentation Software: Energy Code Ace  
 CA Building Energy Efficiency Standards - 2025 Nonresidential Compliance Report Version: 2025.0.000 Compliance ID: ECA-369325-0126-0008  
 Schema Version: rev 20250101 Report Generated: 2026-01-29 10:55:44



Revisions


Delta	Date	Revisions	By

CONSTRUCTION DOCUMENTS

AGENCY APPROVAL

<b>TURLEY MECHANICAL ENGINEERING &amp; ASSOCIATES</b>	
1760 Creekside Oaks Drive Sacramento, CA 95833	(916) 225-5866 Fax: (916) 225-5955 Email: <a href="mailto:office@turley-mech.com">office@turley-mech.com</a>
Project Engineer: NS	Job Number: 25236
Project Manager: NS	Proj Date: Jan 29, 2026 4:16pm
Project Number: 25236	Log: 1/29/26
X-TRK 25236 2026-10-03 2:11	

This document is the property of the Owner and is not to be used without his written permission



HY Architects Project number: 6306









Facility  
 NEW MAIN OFFICE  
 1400 STANFORD RANCH, ROCKLIN CA 95765

Project  
 HVAC PACKAGE UNIT  
 REPLACEMENT

Sheet Title  
 TITLE-24 REPORTS

Client Project Number: N/A

Scale: As indicated Sheet  
 Drawn By: T&A  
 Checked By: T&A  
 Issue Date: JANUARY 30, 2026  
**T-24B**  
 Sheet of



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY

### ABBREVIATIONS

A	AMPERES	MTD.	MOUNTED
AC	ALTERNATING CURRENT	N	NEUTRAL
AMP	AMPERE	(N)	NEW
AWG	AMERICAN WIRE GAUGE	NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
BKR	BREAKER		
C.	CONDUIT	PH	PHASE
C.B.	CIRCUIT BREAKER	RCPT.	RECEPTACLE
CKT	CIRCUIT	SWBD	SWITCHBOARD
(E)	EXISTING	TYP.	TYPICAL
FACP	FIRE ALARM CONTROL PANEL	UL	UNDERWRITERS LABORATORY
GA.	GAUGE	UNO	UNLESS NOTED OTHERWISE
GND	GROUND	V	VOLT
GFCI	GROUND FAULT CIRCUIT INTERRUPTER	W	WIRE, WATT
MIN.	MINIMUM	WP	WEATHER PROTECTED

### ELECTRICAL SYMBOL LIST

	JUNCTION BOX - SIZE AS REQUIRED BY CODE
	GFCI DUPLEX CONVENIENCE OUTLET - NEMA 5-20R
	FIRE ALARM MECHANICAL DUCT DETECTOR. COORDINATE LOCATION WITH HVAC DRAWINGS AND CONTRACTOR.
	SWITCHBOARD, DISTRIBUTION PANEL, OR MOTOR CONTROL CENTER
	EQUIPMENT DISCONNECT SWITCH - EXTERNALLY OPERATED, FUSED WITH FUSE SIZE TO MATCH EQUIPMENT NAMEPLATE.
	MECHANICAL EQUIPMENT DESIGNATION - SEE MECHANICAL PLANS
	CONDUIT AND WIRING
	CONDUIT HOMERUN TO PANELBOARD, SWITCHBOARD OR TERMINAL CABINET
	DRAWING SHEET NUMBERED NOTE DESIGNATION - APPLIES TO NUMBERED NOTE ON SAME SHEET
	DRAWING PLAN OR DETAIL DESIGNATION - "1" OR "A" DENOTES PLAN OR DETAIL NUMBER, "E-1" DENOTES SHEET NUMBER

### ELECTRICAL SHEET INDEX

No. OF SHEETS	DRAWING No.	DRAWING DESCRIPTIONS
1	E0.01	ELECTRICAL COVER SHEET
2	E1.01	SITE PLAN - ELECTRICAL
3	E2.10	ROOF PLAN - DEMOLITION - ELECTRICAL
4	E2.11	ROOF PLAN - REMODEL - ELECTRICAL

### EXISTING LOAD CALCULATION

Project Name: PCOE Stanford Ranch Corp Center HVAC Replacement Date: 18-Feb-26  
Project No. 25281.21 By: M. Neils Engineering, Inc.

Existing maximum demand (based on 12 months readings below):	261.60 KVA
Source: M. Neils Engineering, Inc., PG&E meter # 1009408809	
Jul-24 154.9 Nov-24 205.5 Mar-25 169.0	
Aug-24 184.0 Dec-24 153.2 Apr-25 164.4	
Sep-24 261.6 Jan-25 140.2 May-25 181.7	
Oct-24 212.7 Feb-25 156.9 Jun-25 199.1	
Existing load factor (25%)	65.40 KVA
Existing load (BEING REMOVED)	265.92 KVA
Total EXISTING service load	= 61.08 KVA
New Load (BEING ADDED)	360.64 KVA
Total service load (NEW improvements)	= 360.64 KVA
TOTAL SERVICE LOAD (EXISTING + NEW improvements)	= 421.72 KVA
421.72 KVA at 277/480 V, 3 phase =	507.48 amperes




Existing: 2000A /3 main circuit breaker (Main Switchboard, "MSB")  
Therefore, existing 2000 amperes, 277/480 Volt, 3-phase, 4-wire service has the capacity for the new load.

- #### SYMBOL LIST NOTES:
- "ABC-#" INDICATES PANEL AND CIRCUIT NUMBER.
  - MINIMUM CONDUCTOR SIZE FOR 120V BRANCH CIRCUITS SHALL BE #12 AWG. AT A MINIMUM ALL BRANCH CIRCUITS SHALL CONTAIN 3/4"C, 2#12 AWG AND 1#12 GND UNLESS OTHERWISE INDICATED.
  - EXISTING ELECTRICAL EQUIPMENT, OUTLETS, AND DEVICES ARE SHOWN THE SAME AS NEW, EXCEPT LIGHTLY AND ACCOMPANIED BY (E). SUCH ELECTRICAL EQUIPMENT, OUTLETS, AND DEVICES ARE TO REMAIN AS IS, UNLESS OTHERWISE NOTED ON PLAN OR SPECIFICATION.
  - ELECTRICAL OUTLET BOXES MOUNTED ON OPPOSITE SIDES OF FIRE-RATED WALLS OR PARTITIONS SHALL BE SEPARATED BY A HORIZONTAL DISTANCE OF NOT LESS THAN 24 INCHES PER CBC, WHETHER SHOWN ON THE PLANS OR NOT.
  - VERIFY ON SITE THAT ALL PANELBOARDS HAVE MINIMUM WORKING SPACES PER CODE AND THAT THE DEDICATED PANELBOARD SPACES ARE CLEAR OF ALL DUCTS, PIPING AND EQUIPMENT FOREIGN TO THE PANEL BOARDS. NOTIFY THE ENGINEER FOR CORRECTIVE ACTION IN THE EVENT THAT FOREIGN OBJECTS IMPEDE THE DEDICATED PANELBOARD AREAS.
  - WHERE CONDUIT STUB IS INDICATED, PROVIDE CONDUIT WITH BUSHING AT THE END OF CONDUIT AND PULL ROPE INTO ACCESSIBLE CEILING AREA.

### APPLICABLE CODES AND REGULATIONS

2025	CALIFORNIA ADMINISTRATIVE CODE (PART 1, TITLE 24, CALIFORNIA CODE OF REGULATIONS (CCR)).
2025	CALIFORNIA BUILDING CODE (CBC) - PART 2, TITLE 24, BASED ON THE 2024 INTERNATIONAL BUILDING CODE (IBC).
2025	CALIFORNIA ELECTRICAL CODE (CEC) - PART 3, TITLE 24, BASED ON THE 2023 NATIONAL ELECTRICAL CODE (NEC).
2025	CALIFORNIA MECHANICAL CODE (CMC) - PART 4, TITLE 24, BASED ON THE 2024 UNIFORM MECHANICAL CODE (UMC).
2025	CALIFORNIA PLUMBING CODE (CPC) - PART 5, TITLE 24, BASED ON THE 2024 UNIFORM PLUMBING CODE (UPC).
2025	CALIFORNIA ENERGY CODE - PART 6, TITLE 24
2025	CALIFORNIA FIRE CODE (CFC) - PART 9, TITLE 24, BASED ON THE 2024 INTERNATIONAL FIRE CODE (IFC).
2025	CALIFORNIA GREEN BUILDING STANDARDS CODE (CALGREEN) - PART 11, TITLE 24
2025	NFPA 72 FIRE ALARM CODE
2025	EDITION TITLE 19, CALIFORNIA CODE OF REGULATIONS, PUBLIC SAFETY, STATE FIRE MARSHAL REGULATIONS.
	OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
	ALL APPLICABLE LOCAL AND STATE CODES/REGULATIONS

- ### DEMOLITION GENERAL NOTES
- INFORMATION SHOWN RELATIVE TO EXISTING CONDITIONS IS BASED UPON AVAILABLE RECORDS AND DATA. THEREFORE, IT SHALL BE REGARDED AS AN APPROXIMATION ONLY. CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT. PRIOR TO SUBMITTING BID AND/OR BEFORE START OF ANY ELECTRICAL WORK, INSPECT ALL EXISTING LOCATIONS AND CONDITIONS AND ASCERTAIN WORK REQUIRED TO CLEAR PROJECT AREA OF ALL EXISTING ELECTRICAL ITEMS NOT BEING REUSED OR EXISTING TO REMAIN AS IS. REPORT ALL DISCREPANCIES AND COORDINATE ALL DEMOLITION WORK WITH THE OWNER'S REPRESENTATIVE. MAINTAIN SERVICE TO EXISTING ELECTRICAL EQUIPMENT IN AREAS ADJACENT TO REMODEL AREA, UNLESS OTHERWISE NOTED.
  - PROTECT ALL EXISTING ELECTRICAL EQUIPMENT ON EXISTING WALLS NOT REQUIRED TO BE DEMOLISHED UNLESS OTHERWISE NOTED. REMOVE FROM SITE, ALL ELECTRICAL EQUIPMENT, HARDWARE, AND OTHER ITEMS BEING REMOVED BY CONTRACTOR.
  - CUT, PATCH AND MATCH IN ALL AREAS AFFECTED BY REMOVAL OF ELECTRICAL EQUIPMENT AND DEVICES.
  - CAUSE AS LITTLE INTERFERENCE OR INTERRUPTION OF EXISTING UTILITIES AND SERVICES. SCHEDULE ANY POWER OR OTHER UTILITY SHUTDOWN WITH THE OWNER'S REPRESENTATIVE. SHUTDOWNS WHICH MAY BE REQUIRED SHALL BE PRESENTED IN WRITING TO THE OWNER'S REPRESENTATIVE FOR APPROVAL TWO WEEKS PRIOR TO COMMENCEMENT OF WORK. SHUTDOWN WORK SHALL BE PERFORMED ON OVERTIME HOURS IF SO DIRECTED BY OWNER'S REPRESENTATIVE.
  - DISCONNECT AND REMOVE ALL EXISTING ELECTRICAL EQUIPMENT, DEVICES, CONDUIT, WIRING AND OTHER ELECTRICAL ITEMS, WHETHER SHOWN OR NOT, FROM EXISTING EQUIPMENT BEING REMOVED. MAINTAIN CIRCUIT CONTINUITY TO ALL EXISTING REMAINING DEVICES, UNLESS OTHERWISE NOTED.
  - COORDINATE WITH OTHER TRADES AND PROMPTLY TRANSMIT ALL INFORMATION REQUIRED BY THEM. COORDINATE THE SEQUENCE OF DEMOLITION WITH OTHER TRADES TO ENSURE THAT ALL WORK PROCEEDS WITH A MINIMUM OF INTERFERENCE AND DELAY.
  - RELOCATE ALL CONDUITS THAT ARE TO REMAIN IN SERVICE WHICH ARE IN A LOCATION TO CONFLICT WITH NEW WORK.
  - WHEREVER EXISTING ELECTRICAL DEVICES, PANELS, CONDUITS, CABLES, AND OTHER ITEMS, CONFLICT WITH REMODEL WORK, WHETHER SHOWN OR NOT, RELOCATE THESE ITEMS TO COORDINATE WITH NEW CONSTRUCTION.
  - REUSE EXISTING CONDUITS AND WIRING WHEREVER POSSIBLE UNLESS OTHERWISE NOTED TO BE REMOVED.
  - PROVIDE PROTECTIVE COVERING OVER EXISTING EQUIPMENT WHEN INSTALLING ALL NEW WORK.



#### Revisions

Delta	Date	Revisions	By

### AGENCY APPROVAL

**M. NEILS ENGINEERING, INC.**  
Electrical Engineers | Lighting Designers  
100 Howe Ave., Suite 220A  
Sacramento, CA 95825-8217  
www.mneilsengineering.com  
Tel: 916.923.4400  
PROJECT #: 25281.21



**HIBSER YAMAUCHI Architects, Inc.**  
4602 2nd Street, Suite 3  
Davis, CA 95618  
530.758.1270 tel | 530.758.4789 fax

HY Architects Project number: 6306

Facility: NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project: HVAC PACKAGE UNIT REPLACEMENT

Sheet Title: ELECTRICAL COVER SHEET

Client Project Number: N/A

Scale: As indicated Sheet

Drawn By: NAK

Checked By: SKL








Issue Date: January 30, 2026

E0.01

Sheet of

All changes to these plans must be in writing and must be approved by M. Neils Engineering, Inc. UNAUTHORIZED CHANGES & USES: M. Neils Engineering, Inc. preparing these plans will not be responsible for, or liable for unauthorized changes to or uses to these plans. File #: 2026-0210n-1016a264n





IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY


NUMBERED NOTES

- 1 DISCONNECT AND REMOVE EXISTING DISCONNECT SWITCH. REMOVE EXISTING CONDUCTORS BACK TO MAIN SWITCHBOARD. PROTECT EXISTING CONDUITS TO MAIN SERVICE SWITCHBOARD FOR REUSE.
- 2 DISCONNECT AND REMOVE EXISTING CONDUCTORS AND CONDUIT BACK TO EXISTING DISCONNECT SWITCH.
- 3 DISCONNECT POWER TO EXISTING DUCT SMOKE DETECTORS. COORDINATE WITH FIRE ALARM CONTRACTOR.
- 4 EXISTING RECEPTACLE TO REMAIN. PROTECT DURING CONSTRUCTION.




Revisions			
Delta	Date	Revisions	By

AGENCY APPROVAL



1 ROOF PLAN - DEMOLITION ELECTRICAL  
E2.10 SCALE: 3/32" = 1'-0"

**M. NEILS ENGINEERING INC.**  
Electrical Engineers | Lighting Designers  
100 Howe Ave., Suite 200A  
Sacramento, CA 95825-8217  
www.mneilsengineering.com  
Tel: (916) 923-4400  
PROJECT #: 25281.21



**HY HIBSER YAMAUCHI Architects, Inc.**  
4602 2nd Street, Suite 3  
Davis, CA 95618  
530.758.1270 tel | 530.758.4789 fax

Facility  
NEW MAIN OFFICE  
1400 STANFORD RANCH, ROCKLIN CA 95765

Project  
HVAC PACKAGE UNIT  
REPLACEMENT








Sheet Title  
ROOF PLAN -  
DEMOLITION  
ELECTRICAL

Client Project Number: N/A

Scale: As indicated  
Drawn By: NAK  
Checked By: SKL  
Issue Date: January 30, 2026

Sheet  
**E2.10**  
Sheet of

File: 18\_2026\_E2.10.dwg  
 UNAUTHORIZED CHANGES & USES: M. Neils Engineering, Inc. preparing these plans will not be responsible for, or liable for unauthorized changes to or uses to these plans. All changes to these plans must be in writing and must be approved by M. Neils Engineering, Inc.



IF THIS SHEET IS NOT 30"x42", IT IS A REDUCED PRINT SCALE ACCORDINGLY

NUMBERED NOTES

- 1 PROVIDE NEMA 3R MOTOR RATED FUSED DISCONNECT SWITCH WITH OVERLOAD PROTECTION AND LOCKABLE COVER. PROVIDE WITH FUSES SIZED TO EQUIPMENT NAMEPLATE REQUIREMENT. COORDINATE EXACT LOCATION OF DISCONNECT SWITCH WITH MECHANICAL. OPERABLE HANDLE OF DISCONNECT SWITCH SHALL BE NO HIGHER THAN 6'-6". REFER TO DETAIL "2/E0.01".
- 2 PROVIDE 3" CONDUIT WITH 6 #4/0, AND 1 #2 GND FROM DISCONNECT SWITCH TO "AC/1" CONTROL POWER PANEL. COORDINATE WITH MECHANICAL FOR EXACT LOCATION OF POWER ENTRY. CONDUIT WITHIN UNIT MAY BE FLEXIBLE METAL CONDUIT. CONDUIT EXPOSED TO WEATHER SHALL BE RSC.
- 3 LOCATE AND CONNECT POWER FOR DUCT SMOKE DETECTORS. COORDINATE WITH MECHANICAL AND FIRE ALARM CONTRACTOR.
- 4 LOCATE JUNCTION BOX TO INTERCEPT EXISTING CONDUITS. EXTEND NEW CONDUIT TO NEW DISCONNECT SWITCH.
- 5 SUPPORT NEW 3" RSC CONDUIT ON STRUT CHANNEL ON EXISTING TOP RAIL OF EXISTING STEEL FENCE. REFER TO DETAIL "3/E0.01". SUPPORTS ALONG FENCE THEN ACROSS TO DISCONNECT SWITCH. CONDUIT SHALL BE 6'-8" MINIMUM. PROVIDE SUPPORTS WITHIN 3FT. OF JUNCTION BOX AND CONDUIT BENDS.




Revisions			
Delta	Date	Revisions	By

AGENCY APPROVAL

**M. NEILS ENGINEERING INC.**  
 Electrical Engineers | Lighting Designers  
 100 Howe Ave., Suite 200A  
 Sacramento, CA 95825-8217  
 www.mneilsengineering.com  
 Tel: (916) 923-4400  
 PROJECT #: 25281.21

This document is the property of the Owner and is not to be used without his written permission



**HY HIBSER YAMAUCHI Architects, Inc.**  
 4602 2nd Street, Suite 3  
 Davis, CA 95618  
 530.758.1270 tel | 530.758.4789 fax

HY Architects Project number: 6306

Facility  
 NEW MAIN OFFICE  
 1400 STANFORD RANCH, ROCKLIN CA 95765


Project  
 HVAC PACKAGE UNIT  
 REPLACEMENT

Sheet Title  
 ROOF PLAN - REMODEL  
 ELECTRICAL

Client Project Number: N/A

Scale: As indicated  
 Drawn By: NAK  
 Checked By: SKL  
 Issue Date: January 30, 2026

Sheet  
**E2.11**  
 of



**1 ROOF PLAN - REMODEL ELECTRICAL**  
 E2.11 SCALE: 3/32" = 1'-0"

File: 18\_2026\_230m\_1016a26.dwg  
 UNAUTHORIZED CHANGES & USES: M. Neils Engineering, Inc. preparing these plans will not be responsible for, or liable for unauthorized changes to or uses to these plans. All changes to these plans must be approved by M. Neils Engineering, Inc.